

Purpose: As per CLI-ECA 064-S710 Schedule E Section 5.2 the Owner shall prepare an annual performance report for the authorized system. The report must be submitted to the Director (MECP) on or before April 30 of each year and covers the period from January 1st to December 31st of the preceding calendar year.

Stormwater System ECA#	064-S701
Stormwater System Name	Town of Fort Erie Stormwater Collection System
Stormwater Owner	Corporation of the Town of Fort Erie
Period Reported	January 1, 2024 to December 21, 2024

Include a summary of all monitoring data along with an interpretation of the data and an overview of the condition and operational performance of the Authorized System and any Adverse Effects on the Natural Environment.

Not applicable – waiting for Ministry to issue guidance document.

Include a summary and interpretation of environmental trends based on all monitoring information and data for the previous five (5) year.

Not applicable – waiting for Ministry to issue guidance document.

Include a summary of any operating problems encountered and corrective actions taken.

Date	Location	Issue	Corrective Actions Taken
2024-10-8	28 Courtwright Street	Repair sinkhole at catch basin	Filled with concrete to level with the sidewalk. Work Complete.
2024-10-8	56 Courtwright Street	Repair sinkhole at catch basin	Filled void with metal plate and bricks. Filled with concrete to road surface. Work complete.
2024-7-16	599 Point Abino Road	Storm pump not working	Pump removed and pump chamber cleared of debris. Pump reinstalled and working.
2024-5-27	Klauck Street	Catch basin sunk very low	CB is not in travelled portion of the road and is not affecting drainage. Will be planned for future adjustment.

Include a summary of the calibration, maintenance and repairs carried out on any major structure, equipment, apparatus, mechanism, or thing forming part of the Authorized System.

No calibration requirements at this time. Maintenance and repairs are outlined in other areas of this report.

Include a summary of any complaints related to the Sewage Works received during the reporting period and any steps taken to address the complaints.

Date	Location	Issue	Corrective Actions Taken
2024-12-9	Glenspring Road and Rosewood Avenue	Road flooded	Crew sent to investigate and no flooding found
2024-12-9	116 Lincoln Road East	A lot of water in front of house	No issues upon arrival at 1535
2024-9-26	308 Gorham Road	Catch basin plugged	Crew sent to vacuum catch basin and clear outlet
2024-7-18	359 Albany Street		
2024-7-16	27 Lavinia Street	Storm sewers are clogged in this area	Area inspected and any clogged catch basins cleared
2024-4-15	794 Ferndale Avenue	Storm sewer lid is cracked	Scheduled to be repaired
2024-4-11	64 Derbyshire Drive	Rear yard flooding	Private drainage matter
2024-4-4	3781 Graebar Avenue	Catch basin too low in driveway	Catch basin cannot be adjusted as it would no longer function
2024-1-31	120 Cambridge Road East	Catch basin too low	Catch basin cannot be adjusted as it would no longer function
2024-1-25	403 Belleview Boulevard	Catch basin installed cracking concrete	Private drainage matter
2024-1-11	223 Prospect Point Road South	Water pooling	No storm sewer at this location
2024-11-14	140 Lakewood	Sinkhole	Schedule to be repaired
2024-9-27	Farr Avenue and Ridge Road	Sinkhole	Repairs completed
2024-9-4	Farr Avenue and Ridge Road	Sinkhole	Repairs completed
2024-8-14	Elm Street and South Mill Street	Sinkhole	Patched with hot mix asphalt
2024-7-24	Ridge Road and Farr Avenue	Sinkhole	Patched with hot mix asphalt

Include a summary of all Alterations to the Authorized System within the reporting period that are authorized by this Approval including a list of Alterations that pose a Significant Drinking Water Threat.

No alterations pose a Significant Drinking Water Threat. 2024 alterations summarized below:

Location (Project Name)	Alteration Summary	Status
Idleywylde Street	Replacement of storm sewers on Idleywylde Street (Mary to Gilmore).	Construction Complete.
King Street	Replacement of storm sewers on King Street (Garrison to Albany)	Construction Complete.
Lindbergh/Burbank	Replacement of storm sewers on Lindbergh Drive (Alwin to Burns)	Construction Complete.
Westwind Shores / Thunder Bay	Installation of storm sewers on J. Hamilton Way. Installation of storm sewers on Thunder Bay Road and Burleigh Road South. Installation of superpipes on J. Hamilton Way. Installation of OGS on J. Hamilton Way.	Construction Complete.
Peace Bridge Village Ph 4	Installation of storm sewers on Arthur St., Louisa St., Burwell Street, Arthur Street.	Construction Complete.

Note: Construction project details included in appropriate Ministry Future Alteration Forms.

Include a summary of all spills or abnormal discharge events

No information for the reporting year.

Include a summary of actions taken, including timelines, to improve or correct performance of any aspect of the Authorized System.

No information for the reporting year.

Include a summary of the status of actions for the previous reporting year.

Not applicable – waiting for Ministry to issue guidance document.

This annual performance report of the Authorized System was prepared by Nicholas Chevalier, A.Sc.T., CRS as required by the CLI-ECA 064-S701 Schedule E Section 5.3.2, this report will be made available by June 1st of the same reporting year, to members of the public without charge by publishing the report on the internet.

This report will also be made available on request and without charge, to members of the public who are served by the authorized system.